

General

Rig Name	EDC Rig 12
Rig Category	Work Over
Rig Type	Carrier
Rig HP	740
Year Built	2004
Manufacturer	DRECO
Rated Drilling Depth	12,000 FT
Rig Move Loads	25



Drilling Equipment

Mast height	135.5 FT
Hook Load	175 TON
Setback Load	110 TON
Rotary Table	NATIONAL 27 1/2 INCH
Drawworks	NOV K 750 DD
Drilling Line	1 1/8 INCH
Top Drive / Kelly	Kelly
Mud Pumps	KREMCO 6K 500

Power Supply Equipment

Main Power Supply	2 EA CATERPILLAR 3412 Diesel Engines
Emergency Power Supply	N/A

Well Control Equipment

Annular BOP	SHAFFER 11 INCH X 5,000 PSI WP
Single BOP	N/A
Double BOP	SHAFFER 11 INCH x 10,000 PSI WP
Choke & Kill Manifolds	SHAFFER 5,000 PSI WP
Accumulator Unit	6 Station - 3,000 PSI WP

Down Hole Equipment

Drill Pipes	3 1/2 INCH
Drill Collars	4 3/4 INCH

Storage Facilities

Liquid Mud	240 BBLS
Drill water	240 BBLS

	Rig Site	Main Camp
Fuel	100 BBLS	N/A
Fresh Water	200 BBLS	N/A

Camp Capacity	12 Persons
----------------------	------------