

General

Rig Name	DPS Rig 74
Rig Category	Drilling
Rig Type	Self Elevating
Rig HP	2000 HP
Year Built	2019
Manufacturer	NOV
Rated Drilling Depth	20,000 FT
Rig Move Loads	160

Drilling Equipment

Mast height	157 FT
Hook Load	500 TON
Setback Load	400 TON
Rotary Table	LSPE 37 1/2 INCH
Drawworks	ADS-10SD
Drilling Line	1 1/2 INCH
Top Drive / Kelly	Top Drive VARCO TDS 11SH
Mud Pumps	3 EA CONTINENTAL EMSCO 1600



Power Supply Equipment

Main Power Supply	5 EA CATERPILLAR 3512 Diesel Engines
Emergency Power Supply	1 EA CATERPILLAR C-15
Main Camp Power Supply	2 EA CATERPILLAR C-15
Rig Site Camp Power Supply	2 EA CATERPILLAR C-15

Well Control Equipment

Annular BOP	HYDRILL 13 5/8 INCH X 10,000 PSI WP
Single BOP	N/A
Double BOP	2 EA CAMERON 13 5/8 INCH X 10,000 PSI WP
Choke & Kill Manifolds	4-10K Choke & Kill Manifold
Accumulator Unit	CAD UNIT-900 Gallon 2 Hydraulic reservoir, manual control or remote control hydraulic valves, 3000 & 5000 PSI

Down Hole Equipment

Drill Pipes	5 1/2 INCH - 4 INCH - 2 3/8 INCH
Heavy Weight Drill Pipes	6 5/8 INCH - 5 1/2 INCH - 4 INCH
Drill Collars	9 1/2 INCH - 8 1/2 INCH - 6 1/4 INCH - 4 3/4 INCH - 2 7/8 INCH

Storage Facilities

Liquid Mud	4,000 BBLs
Drill water	2 EA Drill Water Tanks 500 BBLs each

Fuel	1500 BBLs
Fresh Water	188 BBLs (one tank)

Camp Capacity 93 Person

Main Camp

130 BBLs
376 BBLs