General

Rig Name EDC Rig 58 Rig Category Drilling Self Elevating Rig Type 2,000 Rig HP

Year Built 2008

NATIONAL OILWELL VARCO 20,000 FT Manufacturer

Rated Drilling Depth Rig Move Loads 150

Drilling Equipment

Mast height 152 FT Hook Load 589 TON Setback Load 360 TON

Rotary Table NOV D-375 - 37 1/2 INCH

Drawworks NOV 1320 UE Drilling Line 1 1/2 INCH

Top Drive / Kelly Top Drive VARCO TDS 11A

Mud Pumps NOV 12P160

Power Supply Equipment

Main Power Supply 4 EA CATERPILLAR 3512 Diesel Engines Emergency Power Supply N/A

Well Control Equipment

Annular BOP SHAFFER 13 5/8 INCH X 5,000 PSI WP Single BOP CAMERON 13 5/8 INCH X 10,000 PSI WP Double BOP CAMERON 13 5/8 INCH X 10,000 PSI WP Choke & Kill Manifolds QUALITY 4 1/16 INCH X 10,000 PSI WP

8 Station - 3000 PSI WP - 26 x 15 Gallon Bottles Accumulator Unit

Down Hole Equipment

Drill Pipes 5 INCH

Drill Collars 4 3/4 INCH - 6 1/2 INCH - 8 1/4 INCH - 9 1/2 INCH

Storage Facilities

Liquid Mud 3800 BBLS Drill water 1400 BBLS

Main Camp

Rig Site 840 BBLS 200 BBLS Fuel **200 BBLS** 400 BBLS Fresh Water

80 Persons **Camp Capacity**

